No.	Details of work	Unit	Rate	Quantity	Cost
7	Providing wooden plug with rod and locking arrangement.	Lump sum		...	
8	Cutting holes in cross and orifice slabs lump sum.	No.		3	
	Sluice No. 2 as above No. 1 Sluice.				
	Waste weirs.				
1	Earthwork excavation for body wall and returns.	C.yd.		134	
2	Surki concrete for foundation	C.ft.		404	
3	Burnt brick in surki mortar	,,		1,221	
4	Burnt stone slabs 4" to 6" thick ...	Sq.ft.		480	
5	Plastering with surki mortar	Sqr.		15·51	
6	New stone for apron including lead of 2 to 3 miles.	C.yd.		113	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notice dated 12th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 23rd October 1929, for constructing Female Dispensary with out-houses at Sira. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. five hundred in cash or Government Promisery Notes as earnest money and be superscribed "Tender for constructing Female Dispensary with out-houses at Sira" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other ilems, the rates as per schedule of rates will be paid at the descretion of the Executive Engineer.

Abstract estimate of quantities for constructing female dispensary, in-patients' wards and out-houses at Sira, Tumkur District.

No.	Particulars	Unit	Quantity
	Dispensary Building and In-patients' Wards.—		
1	Earthwork excavating foundation and filling in basement ...	C.yd.	91
2	Stone jelly concrete	C.ft.	795
3	Burnt stone in mortar with bond stones for every 6′ in each layer (foundation.)	,,	1,252
4	Do basement	,,	1,077
5	Burnt brick in mortar with bond slabs (superstructure) ...	,,	3,970
6	Providing and fixing cut stone pillar (7′ 8″ Sqr., nicely dressed including base and capitals.)	Each	7
6 (a)	Arch work. Burnt brick in chunam	C.ft.	49
7	Teakwood doors with pannelled shutters and ventilators at top of iron fittings, etc., complete as per Maryat's specification.	S.ft.	370
8	Teakwood windows with pannelled shutters ventilators at top complete as per Maryat's specification (without iron bars.)	...	307
9	Teakwood ventilators	S.ft.	14
10	Teakwood shelves with cross planks	,,	90
11	Teakwood circular ventilators	,,	10
12	Providing and fixing burnt stone slabs 6″ thick including dressing of exposed portions.	,,	537
13	Pointing to basement in cement	Sqr.	4·27
14	Teakwood work wrought and put up including wood oiling ...	C.ft.	141·04
15	Roofing with First Class Mangalore pattern Tumkur tiles on teak reepers (2″ x 1″), the eave tiles being tied up with teak batten screwed down to the rafters.	Sqr.	26·04
16	Ridge and hip tiles set in mortar including cement pointing...	R.ft.	146
17	Providing and fixing teak wood planks ¾″ thick for valleys with wood oiling, etc., complete.	S.ft.	102
18	Providing and fixing zinc sheets for valleys size (22 G) ...	,,	102
19	Providing and fixing teakwood finials including chacolate painting (big).	Each	3
20	Providing and fixing teakwood finials including chacolate painting (small).	,,	1
21	Teakwood pendents including chacolate painting ...	,,	18
22	Preparing and fixing dispensing counter complete ...	,,	2
23	Providing and fixing teakwood ornamental eave board 9″ wide including painting, etc., complete.	R.ft.	281
24	Plastering with chunam mortar	Sqr.	75·93
25	Flooring with First Class Mangalore tiles or burnt stone slabs (Madakanhalli on 3″ concrete bed and cement pointing).	,,	9·26
26	Flooring with 1½″ cuddapah slabs or burnt stone slabs (Madakanhalli) on 3″ concrete bed and cement pointing.	,,	3·37
27	Ornamental work in mortar for the ward windows ...	Lump sum	Rs.
28	Clearing site and levelling ground	,,	,,
29	White washing two coats	Sqr.	75·93
30	Chunam borders (6″ high)	R.ft.	58
31	Providing and fixing teak wood screen in the examination room, painting, etc., complete.	S.ft.	98
32	Constructing sinks	Each	4
33	Tarring to wood work	Lump sum	Rs.
34	Silicate chacolate painting 2 coats	Sqr.	16·29
35	Formation of approach road with necessary gravel, etc., ..	Lump sum	Rs.
36	Providing and fixing date stone	Each	1
37	Providing and fixing a name board	Lump sum	Rs.
38	Constructing lead off drains (a) Raingauge	,,	,,
39	Dismantling and reconstructing raingauge	,,	,,

Sl. No.	Particulars	Unit	Quantity
	II Kitchen :—		
1	Earthwork excavation for foundation	C.yds.	4
2	Burnt stone in clay foundation and basement ...	,,	173
3	Burnt brick in clay superstructure	,,	279
4	Providing and fixing teakwood doors battened shutters, iron work, etc., complete as per Marryat's specification.	S.ft.	18
5	Providing and fixing teak wood windows with battened shutters, iron bars, iron fittings, etc., complete as per Marryats Specification.	,,	12
6	Teakwood work wrought and put up including wood oiling ...	C.ft.	11·66
7	Roofing with Mangalore pattern Tumkur tiles on teak reepers, the eave tiles being tied up by teak batten (2″×1″), screwed down to the rafter.	Sqr.	2·25
8	Ridge tiles set in mortar	R.ft.	15
9	Plastering with chunam mortar	Sqr	5·52
10	Flooring with 1½″ Cuddapha slabs on 3″ concrete bed and cement pointing.	,,	0·70
11	Providing and fixing burnt stone slabs 6″ thick dressed ..	S.ft.	26
12	Pointing to basement with cement	Sqr.	0·43
13	White washing two coats	,,	5·52
14	Sundries and unforeseen works	Lump	sum
15	Chunam borders over roof	R.ft.	30
16	Providing and fixing ventilating tiles each	Each	4
17	Silicate chacolate painting two coats	Sqr.	0 60
	III: *Latrine.*		
1	Constructing two latrines, one for male dispensary and another for female dispensary with the materials available for one and including dismantling the existing latrine.	Lump	sum
	IV. *Dead House.*		
1	Dismantling and reconstructing Dead House as per approved design.	Lump	sum

V. V. PATANKAR,
Executive Engineer.

MENTAL HOSPITAL, BANGALORE.

Dated 16th September 1929.

Sealed tenders, in triplicate, on half sheet foolscap size paper will be received by the Superintendent, Mental Hospital, Bangalore City, at his office up to 11 A.M., on Friday the 15th November 1929, for the supply of diet, contingent articles and weaving materials required for the use of this institution.

For details, please refer to *Mysore Gazette*, Part VI, pages 1009 to 1012, dated 12th September 1929.

F. NORONHA,
Superintendent.